

Complete RV Setup & Tear Down Checklist

Pre-Arrival Checklist

- Confirm campsite reservation and hookup type (30A / 50A).
- Check weather forecast.
- Ensure batteries are charged.
- Verify surge protector and regulator packed.
- Inspect tires and fluid levels.

Arrival & Setup – Level & Stabilize

- Position RV correctly on site.
- Place wheel chocks.
- Level using blocks or auto-level system.
- Deploy stabilizer jacks.

Electrical Setup

- Inspect power pedestal before connecting.
- Connect surge protector.
- Connect shore power cable.
- Turn breaker on after connecting.
- Verify safe voltage reading.

Water Setup

- Attach pressure regulator.
- Connect drinking-water-safe hose.
- Flush hose briefly before connecting.
- Turn water on slowly.
- Check all fittings for leaks.

Sewer Setup

- Connect sewer hose securely.
- Ensure black and gray valves are closed.
- Use sewer hose support if needed.

Departure Checklist

- Turn off and disconnect shore power.
- Disconnect water and drain hose.
- Dump black tank, then gray tank.

- Rinse and store sewer hose.
- Retract stabilizers and remove chocks.
- Final walk-around inspection.